



अन्नपूर्ण गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय
पोखरेवगर, म्याग्दी
२०७३

सम्पर्क नं ९८५७६८३८१० (प्र.प्र.अ)
Email: ito.annamun@gmail.com
Web: annapurnamunmyagdi.gov.np
गण्डकी प्रदेश नेपाल

प.सं. २०८२/०८३

प्रथम पटक प्रकाशित मिति: २०८२/०९/०८


“घारखोला-नेपाने-पाउद्वार मोटरबाटो निर्माण तथा मर्मत” आयोजनाको लागि दररेट पेश गर्ने सम्बन्धी सार्वजनिक सूचना !!!

अन्नपूर्ण गाउँपालिका पोखरेवगर, म्याग्दी अन्तर्गत रहेको वडा नं. ५ **“घारखोला-नेपाने-पाउद्वार मोटरबाटो निर्माण तथा मर्मत”** आयोजनाको लागि इच्छुक फर्म/कम्पनीबाट दररेट पेश गर्ने सम्बन्धी सार्वजनिक सूचना प्रकाशित गरिएको छ। निर्माण कार्यसंग सम्बन्धीत विल अफ क्वान्टीटी (BOQ) फारम अन्नपूर्ण गाउँपालिकाको कार्यालय वा कार्यालयको Website: www.annapurnamunmyagdi.gov.np वाट प्राप्त गर्न सकिने छ। उक्त कार्यको लागि तपसिल वमोजिमका आवश्यक कागजातहरूको प्रमाणपत्रको प्रतिलिपी सहित तोकिएको ढाचामा के कति दर रेटमा काम गर्न सकिन्छ, सोको विल अफ क्वान्टीटी (BOQ) भरि लिखित अनुरोध सहित प्रकाशित सूचनाको मितिले ७ (सात) दिन भित्र पेश गर्नुहुन अनुरोध छ।

क) योजनाको लागत अनुमानित रकम रु. ९८७४३७.९८ (अक्षयरूपी नौ लाख सतासी हजार चार सय सर्तिस रुपैया अन्ठानब्बे पैसा) VAT and PS सहित

तपसिल

१. फर्म/कम्पनी दर्ता एवं नविकरण।
२. आ.व. २०८१/०८२ को कर चुक्ताको प्रमाण पत्र।
३. स्थायी लेखा नं / भ्याटमा दर्ता भएको प्रमाण पत्र।


कपिल पाण्डे
प्रमुख प्रशासकीय अधिकृत

Annapurna Rural Municipality
Office of the Rural Municipal Executive

Pokharebagar, Myagdi
Gandaki Province, Nepal

BILL OF QUANTITY



VNS

कपिल पाण्डे
प्रमुख प्रशासकीय अधिकृत

योजनाको नाम:- धारखोला-नेपाने-पाउद्वार मोटरबाटो निर्माण तथा मर्मत
कार्य गर्ने स्थान:- धारखोला देखि पाउद्वार जाने बाटोमा

अन्नपूर्ण गाउँपालिका-५ नं: वडा, सिन्धु

मिति :- २०८३/०९/०९
आ.ब :- २०८२/०८३

Item No	Description of Works	Unit	Quantity	Rate (Rs.)	Amount (Rs.)	Amount in Word(Rs.)	Remarks
PS Item							
A							
1	Providing and installation of project information board with the size of 1.8 x 1.2 m as per specification and instruction of engineer SS 110	PS	1.00	3000.00	3000	Three Thousand Only	
B	Civil Works						
1	Earth work Excavation for foundation of all type soil by Excavator Machine	Cu.m	11.20				
2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cu.m	22.40				
3	Providing , Preparing and Installing form work including necessary supports and removing after completion for foundation and footings	Sq.m	11.20				
4	Providing and laying ,fitng and placing HYSDB bar reinforcement in sub-structure complete as per drawing and technical Specifications. PROVING AND PLACING OF MIXER MIXED MZU (1:1.5:3) cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete as per specification	Kg	896.00				
5	Providing and laying ,fitng and placing HYSDB bar reinforcement in sub-structure complete as per drawing and technical Specifications. PROVING AND PLACING OF MIXER MIXED MZU (1:1.5:3) cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete as per specification	Cu.m	44.80				
Sub Total Amount					NRS.		
Vat able Amount					NRS.		
Vat 13 %					NRS.		
Total Estimated Amount(A+B+Vat)					NRS.		