



अन्नपूर्ण गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय

पोखरेवगर, म्याग्दी
२०७३
गण्डकी प्रदेश, नेपाल

सम्पर्क नं ९८५७६८३८९० (प्र.प्र.अ)
Email: ito.annamun@gmail.com
Web: annapurnamunmyagdi.gov.np

गण्डकी प्रदेश नेपाल

प.सं. २०८२/०८३
नं. १३६२

प्रथम पटक प्रकाशित मिति: २०८३/०९/१६

“कोप्चेपानी मोटरबाटो निर्माण” आयोजनाको लागि दररेट पेश गर्ने सम्बन्धी सार्वजनिक सूचना।

अन्नपूर्ण गाउँपालिका पोखरेवगर, म्याग्दी अन्तर्गत रहेको वडा नं. ४ कोप्चेपानी मोटरबाटो निर्माण आयोजनाको लागि इच्छुक फर्म/कम्पनीबाट दररेट पेश गर्ने सम्बन्धी सार्वजनिक सूचना प्रकाशित गरिएको छ। निर्माण कार्यसंग सम्बन्धीत विल अफ क्वान्टिटी (BOQ) फारम अन्नपूर्ण गाउँपालिकाको कार्यालय वा कार्यालयको Website: www.annapurnamunmyagdi.gov.np वाट प्राप्त गर्न सकिने छ। उक्त कार्यको लागि तपसिल बमोजिमका आवश्यक कागजातहरूको प्रमाणपत्रको प्रतिलिपी सहित तोकिएको ढाचामा के कति दर रेटमा काम गर्न सकिन्छ सोको विल अफ क्वान्टिटी (BOQ) भरि लिखित अनुरोध सहित प्रकाशित सूचनाको मितिले ७ (सात) दिन भित्र पेश गर्नुहुन अनुरोध छ।

क० योजनाको अनुमानित लागत रकम रु. ९९६८९३.९८ (अक्षयरूपी नौ लाख छयानब्बे हजार आठ सय तिरानब्बे रुपैया अन्ठानब्बे पैसा) VAT and PS सहित ।

तपसिल

१. फर्म/कम्पनी दर्ता एवं नविकरण ।
२. आ.व. २०८१/०८२ को कर चुक्ताको प्रमाण पत्र ।
३. स्थायी लेखा नं / भ्याटमा दर्ता भएको प्रमाण पत्र ।

(Handwritten signature and date)
२०८३/०९/१६

नि.प्रमुख प्रशासकीय अधिकृत

BOQ (Bill of Quantity)


योजनाको नाम : कोचेपानी मोटबाटो निर्माण

स्थान :- अन्नपूर्ण गा पा वडा नं ४ नारच्याङ

स्वीकृत लागत अनुमान :- ९९६८९३.९८ (स्याट र PS सहित)

आ.व.:- ०८२/८३

मिति :- २०८३/०९/१६



 Administrative Officer
 Prabin Pokharel

S.N	Description of work	Quantity	Unit	Rate	Amount	Remarks
A	Provisional sum					
1	Providing and installation of project information board with the size of 1.8 x 1.2 m as per specification and instruction of engineer [SS 110]	1.00	ps	2500.00	2500.00	
2	Insurance for the loss of damage to works, plants, materials, equipment properties and personnel injury or death, including third party insurance as described on Condition of Contract [GCC 19]	1.00	ps	10000.00	10000.00	
B	Construction works				12500.00	
1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. BY labour (Manual Means) In area of light jungle (less than 15 number per 100 sqm)	2280.57	Cum			
	Soft Soil Cutting					
	hard soil cutting	399.34	Cum			
2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	5.04	Cum			
3	Providing and placing of Mixer-mixed M10 (1:3:6) cement concrete for the foundation and footing etc. for Drain Base including compaction, curing, testing and lead 30m. etc. all complete as per specification and drawing.	3.78	Cum			
4	Providing and laying Random rubble stone masonry in cement mortar [cement(1) : sand(6)] in structure complete as per drawing and technical specification with Manual (labour) Mixed Mortar.	54.00	Cum			
	Sub-Total of construction work(B)					
	VAT 13% of Vatable amount ©					
	PS item (A)				12500.00	
	Total amount (A+B+c)					

In words :-